


- site demo keynotes**
1. REMOVE EXISTING SIDEWALK AND BASE COMPLETE.
 2. REMOVE EXISTING LIMESTONE LOW-WALL COMPLETE.
 3. RECONFIGURE IRRIGATION SYSTEM AS REQUIRED, INCLUDING RELOCATING CONTROL BOX AND INSTALL NEW SPRINKLER HEADS (4) PER NEW PLANTING AREAS, SEE NEW IRRIG. SITE PLAN.
 4. REMOVE EXISTING CHAIN LINK MECHANICAL COURTYARD FENCING COMPLETE.
 5. REMOVE EXISTING AIR HANDLING UNIT FADS, REFERENCE MECHANICAL DRAWINGS. REMOVE EXISTING GRAVEL.
 6. REMOVE EXISTING PIPE RAILING COMPLETE.
 7. BLACK OUT EXISTING HANDICAP PARKING SPACE STRIPING AND SYMBOL.
 8. REMOVE EXISTING HANDICAPPED PARKING SIGN.
 9. REMOVE EXISTING CONCRETE STEPS AND LANDINGS COMPLETE.
 10. EXISTING STONE STEPS AND RAILING TO REMAIN.
 11. REMOVE EXISTING CONCRETE CURB.
 12. REMOVE EXISTING LIMESTONE BLOCK COMPLETE.

Issued	_____
Revised	_____
_____	_____
_____	_____
_____	_____



THIS DOCUMENT IS THE PROPERTY OF OREGON GROUP ARCHITECTS. IT IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF OREGON GROUP ARCHITECTS.

OREGON GROUP ARCHITECTS
 ARCHITECTURE INTERIORS CODED/GRAPHICS
 1000 NE PARKWAY DRIVE, SUITE 200
 PORTLAND, OREGON 97232-1211 | P 503-726-8869

renovation of:
clark county courthouse
 101 north limestone street
 springfield, oh 45502

demo site plan

project number	231512
date	11/11/2023
drawn by	_____
checked by	_____
_____	_____

sheet

C1.1